

Sound Proofing:- Interior of side walls and ceiling of Motor Generator Room to be covered with 2-inches of cork-board to deaden sound of motor generator set, - applied as per Johns Mansville, specifications to be furnished; or other suitable material, if approved.

Passageway to Office Building:- Recess and tooth brick work on south face of building, as called for on drawing, to facilitate attaching covered passageway to office building, when constructed at some future date.

Seats to be provided in walls, where indicated, to carry framing of covered passageway.

Waterproofing:- Brick work to be laid so that no water or moisture will come through to the inside face.

Tile Work:- As called for on the plans, lay up 4" T.C. tile partitions, using hard burned terra cotta tile.

All tile to be smooth, both sides and laid on side in mortar same as specified for brick.

All tile to break joints.

Pointing Brick Work:- After the coping blocks, sills, lintels, sash, doors, and all other construction have been set, they are to be neatly pointed up to correspond with the adjacent construction, and made weather-tight.

Miscellaneous Openings:- Provide openings in walls for pipes, ventilators, service system contractors, etc.

Guarantee:- Any brick that spawls or disintegrates due to the